



中国认可
国际互认
检测
TESTING
CNAS L10160

EMC TEST REPORT

For

SRNE Solar Co., Ltd

Solar Charge Controller

Test Model: MF4860N15

Prepared for : SRNE Solar Co., Ltd
Address : 4-5F,13A Wutong Island, Neihuan Rd, Xixiang, Bao'an,
Shenzhen, Guangdong, China

Prepared by : Shenzhen Southern LCS Compliance Testing Laboratory Ltd.
Address : 101-201, No.39 Building, Xialang Industrial Zone, Heshuikou
Community, Matian Street, Guangming District, Shenzhen,
China

Tel : (+86)755-29871520
Fax : (+86)755-29871521
Web : www.LCS-cert.com
Mail : webmaster@LCS-cert.com

Date of receipt of test sample : September 01, 2020
Number of tested samples : 1
Serial number : Prototype
Date of Test : September 01, 2020 ~ September 16, 2020
Date of Report : September 16, 2020



EMC TEST REPORT
EN 61000-6-4:2007-A1:2011
 Electromagnetic compatibility (EMC) - Part 6-4: Generic standards - Emission standard for industrial environments
EN IEC 61000-6-2:2019
 Electromagnetic compatibility (EMC) - Part 6-2: Generic standards - Immunity standard for industrial environments

Report Reference No. : **LCS200901077BE**
Date of Issue..... : September 16, 2020

Testing Laboratory Name..... : **Shenzhen Southern LCS Compliance Testing Laboratory**
Address..... : 101-201, No.39 Building, Xialang Industrial Zone, Heshuikou Community, Matian Street, Guangming District, Shenzhen, China.
Testing Location/ Procedure : Full application of Harmonised standards
 Partial application of Harmonised standards
 Other standard testing method

Applicant's Name : **SRNE Solar Co., Ltd**
Address..... : 4-5F,13A Wutong Island, Neihuan Rd, Xixiang, Bao'an, Shenzhen, Guangdong, China

Test Specification
Standard..... : EN 61000-6-4:2007-A1:2011
 EN IEC 61000-6-2:2019
 EN 61000-3-2: 2014
 EN 61000-3-3: 2013
Test Report Form No...... : LCSEMC-1.0
TRF Originator : Shenzhen Southern LCS Compliance Testing Laboratory Ltd.
Master TRF..... : Dated 2016-08

Shenzhen Southern LCS Compliance Testing Laboratory Ltd. All rights reserved.
 This publication may be reproduced in whole or in part for non-commercial purposes as long as the Shenzhen Southern LCS Compliance Testing Laboratory Ltd. is acknowledged as copyright owner and source of the material. Shenzhen Southern LCS Compliance Testing Laboratory Ltd. takes no responsibility for and will not assume liability for damages resulting from the reader's interpretation of the reproduced material due to its placement and context.

Test Item Description..... : **Solar Charge Controller**
Trade Mark..... : N/A
Test Model..... : MF4860N15
Ratings : Solar Input voltage:≤150V
 Input power:800W/12V;1600W/24V;2400W/36V;3200W/48V
Result : **PASS**

Compiled by:

Supervised by:

Approved by:

Aimee Yang

Dm Gu



Aimee Yang / File administrators

Dm Gu/ Technique principal

Cherry Chen/ Manager

EMC -- TEST REPORT

| | |
|---|--|
| Test Report No. : LCS200901077BE | <p style="text-align: center;"><u>September 16, 2020</u> Date of issue</p> |
|---|--|

| |
|--|
| <p>Applicant..... : SRNE Solar Co., Ltd Address..... : 4-5F,13A Wutong Island, Neihuan Rd, Xixiang, Bao'an, Shenzhen, Guangdong, China Telephone..... : / Fax..... : /</p> |
| <p>Manufacturer..... : SRNE Solar Co., Ltd Address..... : 4-5F,13A Wutong Island, Neihuan Rd, Xixiang, Bao'an, Shenzhen, Guangdong, China Telephone..... : / Fax..... : /</p> |
| <p>Factory..... : SRNE Solar Co., Ltd Address..... : Room 401, building 2, no. 10, xinju road, shangjiao village, chang'an, dongguan, guangdong Telephone..... : / Fax..... : /</p> |

| | |
|--------------------|-------------|
| Test Result | PASS |
|--------------------|-------------|

The test report merely corresponds to the test sample.
 It is not permitted to copy extracts of these test result without the written permission of the test laboratory.

Revision History

| Revision | Issue Date | Revisions | Revised By |
|----------|--------------------|---------------|-------------|
| 000 | September 16, 2020 | Initial Issue | Cherry Chen |
| | | | |
| | | | |

TABLE OF CONTENTS

| | Page |
|---|-----------|
| 1. SUMMARY OF STANDARDS AND RESULTS | 6 |
| 1.1. DESCRIPTION OF STANDARDS AND RESULTS | 6 |
| 2.1. DESCRIPTION OF PERFORMANCE CRITERIA | 7 |
| 2. GENERAL INFORMATION..... | 8 |
| 2.1. DESCRIPTION OF DEVICE (EUT) | 8 |
| 2.2 SUPPORT EQUIPMENT LIST | 8 |
| 2.3. DESCRIPTION OF TEST FACILITY | 8 |
| 2.4. STATEMENT OF THE MEASUREMENT UNCERTAINTY | 8 |
| 2.5. MEASUREMENT UNCERTAINTY | 9 |
| 3. MEASURING DEVICES AND TEST EQUIPMENT | 10 |
| 4. RADIATED EMISSION MEASUREMENT | 11 |
| 4.1. BLOCK DIAGRAM OF TEST SETUP | 11 |
| 4.2. TEST STANDARD | 12 |
| 4.3. EUT CONFIGURATION ON TEST | 12 |
| 4.4. OPERATING CONDITION OF EUT | 12 |
| 4.5. TEST PROCEDURE..... | 12 |
| 4.6. TEST RESULTS..... | 12 |
| 5. ELECTROSTATIC DISCHARGE IMMUNITY TEST..... | 15 |
| 5.1. BLOCK DIAGRAM OF TEST SETUP | 15 |
| 5.2. TEST STANDARD | 15 |
| 5.3. SEVERITY LEVELS AND PERFORMANCE CRITERION | 15 |
| 5.4. EUT CONFIGURATION ON TEST | 15 |
| 5.5. OPERATING CONDITION OF EUT | 15 |
| 5.6. TEST PROCEDURE..... | 16 |
| 5.7. TEST RESULTS..... | 16 |
| 6. RF FIELD STRENGTH SUSCEPTIBILITY TEST | 18 |
| 6.1. BLOCK DIAGRAM OF TEST SETUP | 18 |
| 6.2. TEST STANDARD | 18 |
| 6.3. SEVERITY LEVELS AND PERFORMANCE CRITERION | 18 |
| 6.4. EUT CONFIGURATION ON TEST | 19 |
| 6.5. OPERATING CONDITION OF EUT | 19 |
| 6.6. TEST PROCEDURE..... | 19 |
| 6.7. TEST RESULTS..... | 19 |
| 7. MAGNETIC FIELD SUSCEPTIBILITY TEST | 21 |
| 7.1. BLOCK DIAGRAM OF TEST SETUP | 21 |
| 7.2. TEST STANDARD | 21 |
| 7.3. SEVERITY LEVELS AND PERFORMANCE CRITERION | 21 |
| 7.4. EUT CONFIGURATION ON TEST | 21 |
| 7.5. TEST PROCEDURE..... | 21 |
| 7.6. TEST RESULTS..... | 21 |
| 8. PHOTOGRAPHS OF TEST SETUP..... | 23 |
| 8. PHOTOGRAPHS OF THE EUT | 25 |

1. SUMMARY OF STANDARDS AND RESULTS

1.1. Description of Standards and Results

The EUT have been tested according to the applicable standards as referenced below.

| Emission (EN 61000-6-4:2007-A1:2011) | | | |
|---|------------------------------|-----------------------------|----------------|
| Description of Test Item | Standard | Limits | Results |
| Conducted disturbance at mains terminals | EN 61000-6-4:2007-A1:2011 | ----- | N/A |
| Conducted disturbance at telecommunication port | EN 61000-6-4:2007-A1:2011 | ----- | N/A |
| Radiated disturbance | EN 61000-6-4:2007-A1:2011 | ----- | PASS |
| Harmonic current emissions | EN 61000-3-2: 2014 | Class A | N/A |
| Voltage fluctuations & flicker | EN 61000-3-3: 2013 | ----- | N/A |
| Immunity (EN IEC 61000-6-2:2019) | | | |
| Description of Test Item | Basic Standard | Performance Criteria | Results |
| Electrostatic discharge (ESD) | EN 61000-4-2: 2009 | B | PASS |
| Radio-frequency, Continuous radiated disturbance | EN 61000-4-3: 2006+A2: 2010 | A | PASS |
| Electrical fast transient (EFT) | EN 61000-4-4: 2012 | B | N/A |
| Surge (Input d.c. power ports) | EN 61000-4-5: 2014+A1: 2017 | B | N/A |
| Surge (Telecommunication ports) | | B | N/A |
| Radio-frequency, Continuous conducted disturbance | EN 61000-4-6: 2014 | A | N/A |
| Power frequency magnetic field | EN 61000-4-8: 2010 | A | PASS |
| Voltage dips, >95% reduction | EN 61000-4-11: 2004+A1: 2017 | B | N/A |
| Voltage dips, 30% reduction | | C | N/A |
| Voltage interruptions | | C | N/A |
| Note 1: N/A is an abbreviation for not applicable. | | | |
| Note 2: systems with nominal voltages less than but not equal to 220 V (line-to-neutral), the harmonic and flicker limits have not yet been considered. | | | |

2.1. Description of Performance Criteria

A functional description and a definition of specific performance criteria, during or as a consequence of immunity testing of equipment under test (EUT), shall be provided by the manufacturer and noted in the test report. They shall be consistent with one of the following general criteria for each test as specified in Table 1 to Table 4:

1.2.1. Performance criterion A

The EUT shall continue to operate as intended during and after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the EUT is used as intended. If the performance level is not specified by the manufacturer, this may be derived from the product description and documentation and what the user may reasonably expect from the equipment if used as intended.

1.2.2. Performance criterion B

The EUT shall continue to operate as intended after the test. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer, when the EUT is used as intended. The performance level may be replaced by a permissible loss of performance. However, during the test degradation of performance is allowed but no change of actual operating state or stored data is allowed. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, either of these may be derived from the product description and documentation and what the user may reasonably expect from the equipment if used as intended.

1.2.3. Performance criterion C

Temporary loss of function is allowed during the test, provided the function is self-recoverable or can be restored by the operation of the controls.

If, as a result of the application of the tests defined in this standard, the EUT becomes dangerous or unsafe, it shall be deemed to have failed the test.

2. GENERAL INFORMATION

2.1. Description of Device (EUT)

EUT : Solar Charge Controller
 Test Model : MF4860N15
 Power Supply : Solar Input voltage: $\leq 150V$
 : Input power: 800W/12V; 1600W/24V; 2400W/36V; 3200W/48V
 EUT Clock Frequency : $\leq 108MHz$

2.2 Support equipment List

| Description | Manufacturer | Model | Serial Number |
|-------------|--------------|-------|---------------|
| | | | |

2.3. Description of Test Facility

EMC Lab. : TUV RH Registration Number. is UA 50418075 0001.
 UL Registration Number. is 100571-492.
 NVLAP Registration Code is 600112-0.
 Test Facilities : Shenzhen Southern LCS Compliance Testing Laboratory Ltd.
 101-201, No.39 Building, Xialang Industrial Zone, Heshuikou
 Community, Matian Street, Guangming District, Shenzhen, China.
 RF Field Strength : Shenzhen LCS Compliance Testing Laboratory Ltd.
 Susceptibility : 101, 201 Building A and 301 Building C, Juji Industrial Park,
 Yabianxueziwei, Shajing Street, Baoan District, Shenzhen,
 Guangdong, China

2.4. Statement of The Measurement Uncertainty

The data and results referenced in this document are true and accurate. The reader is cautioned that there may be errors within the calibration limits of the equipment and facilities. The measurement uncertainty was calculated for all measurements listed in this test report acc. To CISPR 16 – 4 “Specification for radio disturbance and immunity measuring apparatus and methods – Part 4: Uncertainty in EMC Measurements” and is documented in the LCS quality system acc. To DIN EN ISO/IEC 17025. Furthermore, component and process variability of devices similar to that tested may result in additional deviation. The manufacturer has the sole responsibility of continued compliance of the device.

2.5. Measurement Uncertainty

| Test | Parameters | Expanded uncertainty (U_{lab}) | Expanded uncertainty (U_{cispr}) |
|---|---|---------------------------------------|---|
| Conducted Emission | Level accuracy (9kHz to 150kHz) (150kHz to 30MHz) | ± 2.63 dB ± 2.35 dB | ± 3.8 dB ± 3.4 dB |
| Power disturbance | Level accuracy (30MHz to 300MHz) | ± 2.90 dB | ± 4.5 dB |
| Electromagnetic Radiated Emission (3-loop) | Level accuracy (9kHz to 30MHz) | ± 3.60 dB | ± 3.3 dB |
| Radiated Emission | Level accuracy (9kHz to 30MHz) | ± 3.68 dB | N/A |
| Radiated Emission | Level accuracy (30MHz to 1000MHz) | ± 3.48 dB | ± 5.3 dB |
| Radiated Emission | Level accuracy (above 1000MHz) | ± 3.90 dB | ± 5.2 dB |
| Harmonic | Voltage | $\pm 0.510\%$ | N/A |
| Voltage Fluctuations & Flicker | Voltage | $\pm 0.510\%$ | N/A |
| <p>1) Where relevant, the following measurement uncertainty levels have been estimated for tests performed on the apparatus.</p> <p>2) The reported expanded uncertainty of measurement is stated as the standard uncertainty of measurement multiplied by the coverage factor of $k=2$, which for a normal distribution corresponds to a coverage probability of approximately 95%.</p> | | | |

3. MEASURING DEVICES AND TEST EQUIPMENT

Radiated Disturbance

| Item | Test Equipment | Manufacturer | Model No. | Serial No. | Due Date. |
|------|--------------------------|-------------------|--------------|---------------|------------|
| 1 | 3m Semi Anechoic Chamber | SIDT FRANKONIA | SAC-3M | 03CH03-HY | 2021-08-05 |
| 2 | EMI Test Receiver | R&S | ESCI | 101010 | 2021-06-17 |
| 3 | Log per Antenna | SCHWARZBECK | VULB9163 | 5094 | 2022-06-23 |
| 4 | EMI Test Software | AUDIX | E3 | N/A | 2021-06-17 |
| 5 | Positioning Controller | MF | BK8807-4A-2T | 2016-0808-008 | 2021-06-17 |
| 6 | Horn antenna | EMCO | 3115 | 00034771 | 2021-06-25 |
| 7 | Preamplifier | QuieTek | QTK-A2525G | CHM/0809065 | 2021-06-25 |

Electrostatic Discharge Immunity Test (ESD)

| Item | Test Equipment | Manufacturer | Model No. | Serial No. | Due Date. |
|------|----------------|--------------|-----------|------------|------------|
| 1 | ESD Simulator | KIKUSUI | KES4021 | KC001311 | 2021-06-19 |

Power Frequency Magnetic Field Immunity Test


| Item | Test Equipment | Manufacturer | Model No. | Serial No. | Due Date. |
|------|--|--------------|-----------|------------|------------|
| 1 | Power frequency mag-field generator System | HTEC | HPFMF100 | 100-2400 | 2021-06-17 |

Radiated, Radio-Frequency, Electromagnetic Field Immunity Test (RS)-LCS


| Item | Test Equipment | Manufacturer | Model No. | Serial No. | Due Date. |
|------|--|-------------------|-----------|------------|------------|
| 1 | RS Test Software | Tonscend | / | / | N/A |
| 2 | ESG Vector Signal Generator | Agilent | E4438C | MY42081396 | 2021-11-14 |
| 3 | 3m Semi Anechoic Chamber | SIDT FRANKONIA | SAC-3M | 03CH03-HY | 2023-06-11 |
| 4 | RF POWER AMPLIFIER | OPHIR | 5225R | 1052 | 2020-11-21 |
| 5 | RF POWER AMPLIFIER | OPHIR | 5273F | 1019 | 2020-11-21 |
| 6 | Stacked Broadband Log Periodic Antenna | SCHWARZBECK | STLP 9128 | 9128ES-145 | 2020-11-21 |
| 7 | Stacked Mikrowellen Log.-Per Antenna | SCHWARZBECK | STLP 9149 | 9149-484 | 2020-11-21 |
| 8 | RS Test Software | Tonscend | / | / | 2021-03-24 |

4. RADIATED EMISSION MEASUREMENT

4.1. Block Diagram of Test Setup



Below 1GHz



Above 1GHz

4.2. Test Standard

EN 61000-6-4:2007-A1:2011

| Limits for Radiated Emission Below 1GHz | | | |
|---|-------------------|--------------------------------------|------------------------------|
| Frequency (MHz) | Distance (Meters) | Field Strengths Limit (dB μ V/m) | |
| 30 ~ 230 | 3 | 50 | |
| 230 ~ 1000 | 3 | 57 | |
| Note: (1) The smaller limit shall apply at the combination point between two frequency bands. (2) Distance refers to the distance in meters between the measuring instrument antenna and the closed point of any part of the EUT. | | | |
| Limits for Radiated Emission Above 1GHz | | | |
| Frequency (MHz) | Distance (Meters) | Peak Limit (dB μ V/m) | Average Limit (dB μ V/m) |
| 1000 ~ 3000 | 3 | 76 | 56 |
| 3000 ~ 6000 | 3 | 80 | 60 |
| ***Note: The lower limit applies at the transition frequency. | | | |

4.3. EUT Configuration on Test

The EN 61000-6-4 regulations test method must be used to find the maximum emission during radiated emission measurement.

4.4. Operating Condition of EUT

- 1) Turn on the power.
- 2) Let the EUT work and measure it.

4.5. Test Procedure

The EUT is placed on a turntable, which is 0.8 meter high above the ground. The turntable can rotate 360 degrees to determine the position of the maximum emission level. The EUT is set 3 meters away from the receiving antenna, which is mounted on a antenna tower. The antenna can be moved up and down from 1 to 4 meters to find out the maximum emission level. By-log antenna is used as a receiving antenna. Both horizontal and vertical polarization of the antenna is set on test.

The bandwidth of the EMI test receiver is set at RBW/VBW=120kHz/1000kHz.

The frequency range from 30MHz to 1000MHz is checked.

The bandwidth of the Spectrum analyzer is set at RBW/VBW=1MHz/3MHz.

The frequency range from 1GHz to the frequency which about 5th carrier harmonic or 6GHz is checked.

4.6. Test Results

PASS.

The test result please refer to the next page.

| | | | |
|---------------------------------|----------------|--------------------------|------------|
| Test Model | MF4860N15 | Test Mode | Working |
| Environmental Conditions | 23.8°C, 53% RH | Detector Function | Quasi-peak |
| Pol. | Vertical | Distance | 3m |
| Test Engineer | Link Li | Test Voltage | DC 48V |



| No. | Mk. | Freq. MHz | Reading Level dBuV | Correct Factor dB/m | Measure- ment dBuV/m | Limit dBuV/m | Margin dB | Detector | Antenna Height cm | Table Degree | Comment |
|-----|-----|--------------|--------------------------|---------------------------|----------------------------|-----------------|--------------|----------|-------------------------|-----------------|---------|
| 1 | | 34.2760 | 13.64 | 13.84 | 27.48 | 50.00 | -22.52 | QP | | | |
| 2 | | 81.7833 | 26.43 | 9.47 | 35.90 | 50.00 | -14.10 | QP | | | |
| 3 | | 95.8882 | 26.31 | 10.22 | 36.53 | 50.00 | -13.47 | QP | | | |
| 4 | * | 143.8295 | 28.26 | 13.54 | 41.80 | 50.00 | -8.20 | QP | | | |
| 5 | | 191.7450 | 17.33 | 10.05 | 27.38 | 50.00 | -22.62 | QP | | | |
| 6 | | 287.7381 | 8.09 | 12.42 | 20.51 | 57.00 | -36.49 | QP | | | |

Remark: Pre-San all mode, Thus record worse case mode result in this report

| | | | |
|---------------------------------|----------------|--------------------------|------------|
| Test Model | MF4860N15 | Test Mode | Working |
| Environmental Conditions | 23.8°C, 53% RH | Detector Function | Quasi-peak |
| Pol. | Horizontal | Distance | 3m |
| Test Engineer | Link Li | Test Voltage | DC 48V |




| No. | Mk. | Freq. MHz | Reading Level dBuV | Correct Factor dB/m | Measure- ment dBuV/m | Limit dBuV/m | Margin dB | Antenna Height cm | Table Degree | Detector | Comment |
|-----|-----|--------------|--------------------------|---------------------------|----------------------------|-----------------|--------------|-------------------------|-----------------|----------|---------|
| 1 | | 81.2117 | 29.94 | 9.46 | 39.40 | 50.00 | -10.60 | | | QP | |
| 2 | * | 95.8882 | 27.39 | 12.41 | 39.80 | 50.00 | -10.20 | | | QP | |
| 3 | | 143.8295 | 25.22 | 9.68 | 34.90 | 50.00 | -15.10 | | | QP | |
| 4 | | 191.7450 | 15.18 | 11.32 | 26.50 | 50.00 | -23.50 | | | QP | |
| 5 | | 287.7381 | 9.64 | 13.06 | 22.70 | 57.00 | -34.30 | | | QP | |
| 6 | | 383.7636 | 12.47 | 15.23 | 27.70 | 57.00 | -29.30 | | | QP | |

Remark: Pre-San all mode, Thus record worse case mode result in this report

5. ELECTROSTATIC DISCHARGE IMMUNITY TEST

5.1. Block Diagram of Test Setup



5.2. Test Standard

EN IEC 61000-6-2:2019

5.3. Severity Levels and Performance Criterion

5.3.1. Severity level

| Level | Test Voltage Contact Discharge (KV) | Test Voltage Air Discharge (KV) |
|-------|-------------------------------------|---------------------------------|
| 1 | ±2 | ±2 |
| 2 | ±4 | ±4 |
| 3 | ±6 | ±8 |
| 4 | ±8 | ±15 |
| X | Special | Special |

5.3.2. Performance Criterion: B

5.4. EUT Configuration on Test

The configuration of EUT is listed in Section 4.3.

5.5. Operating Condition of EUT

Same as conducted emission measurement, which is listed in Section 3.4. Except the test set up replaced by Section 8.1.

5.6. Test Procedure

5.6.1. Air Discharge

This test is done on a non-conductive surface. The round discharge tip of the discharge electrode shall be approached as fast as possible to touch the EUT. After each discharge, the discharge electrode shall be removed from the EUT. The generator is then re-triggered for a new single discharge and repeated 10 times for each pre-selected test point. This procedure shall be repeated until all the air discharge completed

5.6.2. Contact Discharge

All the procedure shall be same as Section 9.6.1. Except that the tip of the discharge electrode shall touch the EUT before the discharge switch is operated.

5.6.3. Indirect Discharge For Horizontal Coupling Plane

At least 10 single discharges (in the most sensitive polarity) shall be applied at the front edge of each HCP opposite the center point of each unit (if applicable) of the EUT and 0.1m from the front of the EUT. The long axis of the discharge electrode shall be in the plane of the HCP and perpendicular to its front edge during the discharge.

5.6.4. Indirect Discharge For Vertical Coupling Plane

At least 10 single discharge (in the most sensitive polarity) shall be applied to the center of one vertical edge of the coupling plane. The coupling plane, of dimensions 0.5m X 0.5m, is placed parallel to, and positioned at a distance of 0.1m from the EUT. Discharges shall be applied to the coupling plane, with this plane in sufficient different positions that the four faces of the EUT are completely illuminated.

5.7. Test Results

PASS.

The test result please refer to the next page.

Electrostatic Discharge Test Results

| | | |
|---------------------|--|--|
| Standard | <input type="checkbox"/> IEC 61000-4-2 | <input checked="" type="checkbox"/> EN 61000-4-2 |
| Applicant | SRNE Solar Co., Ltd | |
| EUT | Solar Charge Controller | Temperature 23.6°C |
| M/N | MF4860N15 | Humidity 53.2% |
| Criterion | B | Pressure 1021mbar |
| Test Mode | Working | Test Engineer Link Li |
| Test Voltage | DC 48V | |

Air Discharge

| Test Points | Test Levels | | | Results | | |
|-------------|-------------------------------------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|--|
| | ± 2kV | ± 4kV | ± 8kV | Passed | Fail | Performance Criterion |
| Front | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Top | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Bottom | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

Contact Discharge

| Test Points | Test Levels | | Results | | |
|-------------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|--|
| | ± 2 kV | ±4 kV | Passed | Fail | Performance Criterion |
| Front | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Top | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Bottom | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

Discharge To Horizontal Coupling Plane


| Side of EUT | Test Levels | | Results | | |
|-------------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|--|
| | ± 2 kV | ± 4 kV | Passed | Fail | Performance Criterion |
| Front | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

Discharge To Vertical Coupling Plane

| Side of EUT | Test Levels | | Results | | |
|-------------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|--|
| | ± 2 kV | ± 4 kV | Passed | Fail | Performance Criterion |
| Front | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Back | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Left | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |
| Right | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> A <input checked="" type="checkbox"/> B |

6. RF FIELD STRENGTH SUSCEPTIBILITY TEST

6.1. Block Diagram of Test Setup



6.2. Test Standard

EN IEC 61000-6-2:2019

6.3. Severity Levels and Performance Criterion

6.3.1. Severity level

| Level | Field Strength (V/m) |
|-------|----------------------|
| 1 | 1 |
| 2 | 3 |
| 3 | 10 |
| X | 1 |

6.3.2. Performance Criterion: A

6.4. EUT Configuration on Test

The configuration of EUT is listed in Section 4.3.

6.5. Operating Condition of EUT

Same as radiated emission measurement, which is listed in Section 5.1, except the test setup replaced as Section 9.1.

6.6. Test Procedure

The EUT are placed on a table, which is 0.8 meter high above the ground. The EUT is set 3 meters away from the transmitting antenna, which is mounted on an antenna tower. Both horizontal and vertical polarization of the antenna is set on test. Each of the four sides of the EUT must be faced this transmitting antenna and measured individually.

In order to judge the EUT performance, a CCD Recording is used to monitor its screen.

All the scanning conditions are as following:

| Condition of Test | Remark |
|-----------------------------------|--------------------------|
| Fielded Strength | 3 V/m (Severity Level 2) |
| Radiated Signal | Unmodulated |
| Test Frequency Range (swept test) | 80-1000MHz,1400-6000MHz |
| Dwell time of radiated | 0.0015 decade/s |
| Waiting Time | 3 Sec. |

6.7. Test Results

PASS.

The test result please refer to the next page.

RF Field Strength Susceptibility Test Results

| | | | |
|-----------------------|--|----------------------|------------|
| Standard | <input type="checkbox"/> IEC 61000-4-3 <input checked="" type="checkbox"/> EN 61000-4-3 | | |
| Applicant | SRNE Solar Co., Ltd | | |
| EUT | Solar Charge Controller | Temperature | 24.1°C |
| M/N | MF4860N15 | Humidity | 52.6% |
| Field Strength | 10V/m 3V/m | Criterion | A |
| Test Mode | Working | Test Engineer | Jason deng |
| Test Frequency | 80MHz to 1000MHz (10V/m) 1400MHz to 6000MHz (3V/m) | Test Voltage | DC 48V |
| Modulation | <input type="checkbox"/> None <input type="checkbox"/> Pulse <input checked="" type="checkbox"/> AM 1KHz 80% | | |
| Steps | 1% | | |

| | Horizontal | Vertical |
|--------------|------------|----------|
| Front | PASS | PASS |
| Right | PASS | PASS |
| Rear | PASS | PASS |
| Left | PASS | PASS |


Test Equipment:

1. Signal Generator: 2031 (MARCONI)
2. Power Amplifier: 500A100 & 100W/1000M1 (A&R)
3. Power Antenna: 3108 (EMCO) & AT1080 (A&R)
4. Field Monitor: FM2000 (A&R)

Note:

7. MAGNETIC FIELD SUSCEPTIBILITY TEST

7.1. Block Diagram of Test Setup



7.2. Test Standard

EN IEC 61000-6-2:2019

7.3. Severity Levels and Performance Criterion

7.3.1. Severity level

| Level | Field Strength (A/m) |
|-------|----------------------|
| 1 | 1 |
| 2 | 3 |
| 3 | 10 |
| 4 | 30 |
| 5 | 100 |
| X | Special |

7.3.2. Performance Criterion: A

7.4. EUT Configuration on Test

The configuration of EUT is listed in Section 3.3.

7.5. Test Procedure

The EUT is placed in the middle of a induction coil (1*1m), under which is a 1*1*0.1m (high) table, this small table is also placed on a larger table, 0.8 m above the ground. Both horizontal and vertical polarization of the induction coil is set on test, so that each side of the EUT is affected by the magnetic field. Also can reach the same aim by change the position of the EUT.

7.6. Test Results

PASS.

The test result please refer to the next page.


Magnetic Field Immunity Test Result

| | | | |
|----------------------|--|---------------------|--------|
| Standard | <input type="checkbox"/> IEC 61000-4-8 <input checked="" type="checkbox"/> EN 61000-4-8 | | |
| Applicant | SRNE Solar Co., Ltd | | |
| EUT | Solar Charge Controller | Temperature | 22.8°C |
| M/N | MF4860N15 | Humidity | 53.2% |
| Test Mode | Working | Criterion | A |
| Test Engineer | Link Li | Test Voltage | DC 48V |

| Test Level (A/M) | Testing Duration | Coil Orientation | Criterion | Result |
|------------------|------------------|------------------|-----------|--------|
| 30 | 5 mins | X | A | PASS |
| 30 | 5 mins | Y | A | PASS |
| 30 | 5 mins | Z | A | PASS |

Note:

8. PHOTOGRAPHS OF TEST SETUP



Test Setup Photo of Radiated Measurement (30MHz~1GHz)



Test Setup Photo of Electrostatic Discharge Test



Test Setup Photo of Magnetic Field Immunity Test

8. PHOTOGRAPHS OF THE EUT



Fig. 1



Fig. 2




Fig. 3




Fig. 4



Fig. 5




Fig. 6




Fig. 7




Fig. 8




Fig. 9




Fig. 10




Fig. 11




Fig. 12

----- THE END OF TEST REPORT -----